ENGINEERING DEPARTMENT.

WATER SUPPLY DIVISION, BANGALORE.

Abstract Notification.

The attention of the public is hereby invited to the notification published in the *Mysore Gazette* of 30th November 1939, Part VI, pages 2409-2410, regarding the Contract for carting work in the Water Supply Division for the year 1940.

The earnest money to be paid with the tender is Rs. 25. Tenders are received till 4 P.M. of 15th December 1939.

Notification dated 11th December 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, Bangalore, up to 4 P.M. on 2nd January 1940, for converting the Executive Engineer's Office at Thippagondanahalli into II Class Travellers' Bungalow, etc. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 270 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for converting the Executive Engineer's Office at Thippagondanahalli into II Class Travellers' Bungalow, etc., in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Estimate for converting the Executive Engineer's Office at Thippagondanahalli into a II Class Travellers' Bungalow, etc.

Item No.	Description of work	Unit	Rate	Quantity	Cost
	Main Building.		Rs. a. p.		Rs.
1	Earthwork excavation for foundation in gravelly soil and filling in basement	C.yd.	0 3 0	31	
2	Burnt stone jelly in chunam	C.ft.	0 4 0	147	
3	Size stone in mortar with bond stones 6 ft. apart foundation and basement	,,	0 4 0	425	
4	Burnt brick in mortar-superstructure	,,	0 4 0	575	
5	Burnt stone slabs 5 to 6" thick roughly dressed and fixed	S.ft. ..	0 6 0	24	

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
6	Providing new teakwood door with battened shutters, hinges, bolts, pad locks, etc. (as per specifications)	S.ft.	1 2 0	58	
7	Chunam plastering ¾″ thick	Sqr.	3 4 0	10·00	
8	Flooring with cement baby jelly concrete 1½″ to 2″ after removing old mortar plastering and cement plastering ½″ thick including cutting lines mixed with red colour	,,	15 0 0	19·16	
9	Painting doors and windows with green paint manufactured at the Industrial Testing Laboratory two coats	,,	3 8 0	12·06	
10	Repairing the present Mangalore tiled room with necessary teak reepers	,,	8 0 0	23·00	
11	Repairing terrace front and rear with two courses of flat tiles and chunam plastering etc. complete	,,	15 0 0	5·10	
12	Whitewashing two coats	,,	0 4 0	112·66	
	Out-house.				
1	Earthwork excavation foundation in gravelly soil and filling in basement	C.yd.	0 3 0	53	
2	Burnt stone jelly in lime mortar concrete for foundation	C.ft.	0 4 0	309	
3	Size stone in clay with bond stones 6 feet apart	,,	0 3 6	1,171	
4	Burnt brick in clay-superstructire	,,	0 2 9	1,806	
5	Burnt stone slabs 6″ thick roughly dressed and fixed	S.ft.	0 6 0	349	
6	Teakwood doors with battened shutters, hinges, bolts, pad locks, etc. complete (as per specifications)	,,	1 2 0	228	
7	Teakwood windows with battened shutters with ¾″ iron bars, etc. complete (shutters in 4 halves) as per specifications	S.ft.	1 6 0	68	
8	Roofing with 1st class Mangalore tiles over 2″×1″ teak reepers and eaves protected with a reaper	Sqr.	25 0 0	11·88	
9	Ridge tiles set in mortar	R.ft.	0 7 6	47½	
10	Teakwood work wrought and put up with two coats of wood oiling and tarring	C.ft.	5 0 0	97·8	
11	Teakwood eave boards 9″×1″ with painting	R.ft.	0 8 0	95	
12	Providing mortar bonds complete	,,	0 4 0	100	
13	Chunam plastering ¾″ thick	Sqr.	3 4 0	35·35	
14	Flooring with 1½″ to 2″ baby jelly cement concrete over 3″ lime concrete and cement mortar plastering ½″ including cutting lines mixed with red colour	,,	20 0 0	5·48	
15	Constructing sinks in bath and kitchen	Each	10 0 0	4	
16	Constructing hearth and platforms	,,	10 0 0	2	
17	Supplying and fixing 1½″ G. I. drain pipes	,,	2 0 0	4	
18	Painting doors and windows with green paint manufactured at the Industrial Testing Laboratory—two coats	Sqr.	3 8 0	5·90	
19	Whitewashing 2 coats	,,	0 4 0	35.35	
20	Providing mortar and pestle	Each	5 0 0	2	
21	Teakwood partition with hinges and a dood in centre etc., complete with wood oiling	S.ft.	1 0 0	105	
	Constructing a non-vegetarian kitchen block for the Inspection Bungalow at Thippagondanahalli.				
1	Earthwork excavation foundation in gravelly soil and filling in basement	C.yd.	0 3 0	14	
2	Size stone in clay with bond slabs 6 feet apart—foundation and basement	C.ft.	0 3 6	601	
3	Size stone in clay for superstructure with bond stones 6 feet apart or	C.ft.	0 3 6	1,073	
3a	Burnt brick in clay for superstructure	,,	0 2 9	1,073	
4	Burnt stone slabs 6″ thick roughly dressed and fixed	S.ft.	0 6 0	79	
5	Teakwood doors with battened shutters, hinges, bolts, padlocks, etc., complete (as per specifications)	,,	1 2 0	46	

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
6	Teakwood windows with battened shutters with ¾″ iron bars, etc., complete (shutters in four halves) as per specifications	S.ft.	1 6 0	32	
7	Teakwood work wrought and put up with two coats of wood oiling and tarring	C.ft.	5 6 0	31.14	
8	Roofing with 1st class Mangalore tiles on 2″×1″ teak reepers and eaves protected with a reaper ..	Sqr.	25 0 0	4.85	
9	Ridge tiles set in mortar	R.ft.	0 7 6	61	
10	Teakwood plain eave board 9″×1″ with painting ..	„	0 8 0	83	
11	Chunam plastering ¾″ thick	Sqr.	3 4 0	6.97	
12	Flooring with 1½″ to 2″ baby jelly cement concrete over 3″ lime concrete and cement mortar plastering ½″ including cutting lines mixed with red colour ..	„	20 0 0	1.48	
13	Pointing with cement	„	3 4 0	7.65	
14	Painting doors, windows, etc., with green paint manufactured at the Industrial Testing Laboratory—two coats	„	3 8 0	8.02	
15	Whitewashing 2 coats	„	0 4 0	6.97	
16	Supplying and fixing 1½″ G. I. drain pipes	Each	2 0 0	5	

M. K. NARASIMHA IYER,
Executive Engineer.

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 5th December 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 20th December 1939, for constructing Sylk pattern drains in Chikballapur Town for the year 1939-40. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1940.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 380 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing Sylk pattern drains in Chikballapur Town for the year 1939--40," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.